**Project: 97 Williston Rd** 

**Contractor: Boston Exterior Remodeling** 

## Scope of work:

- -Remove the existing vinyl siding on home.
- -Existing siding is 5" clapboard. We will replicate the exiting 5" clapboard in primed, finger-jolted cedar clapboard.
- -Install 5/4" 5" window trims with 1 3/4" band moulding historical sill, all made from real wood.
- -New underlayments
- -House has evidence of a water table at the foundation. This will be replicated.
- -The house will be sanded, primed, and painted.
- -Historical details of home will be preserved
- -Will paint the home Benjamin Moore Historic Collection color.
- -Black windows, 6 over 1 grids

